

Special Requirements for Development Projects (Cont)

9. For asphalt concrete the exact proportions of aggregate and the amount of asphalt binder for each type of mixture shall be regulated as directed by the City Engineer. However, as a general guideline, the required asphalt content for the City of Huntington Beach asphalt concrete mix designs will be as follows:

Arterial Highways


3/4" (III-B-2) Base Course	5.4%
1/2" (III-C-3) Surface Course	5.8%

Non-Arterial Highways

3/4" (III-B-3) Base Course	5.7%
1/2" (III-C-3) Surface Course	6.0%

10. As-Built plans shall be submitted.

APPROVED:



CITY ENGINEER

REVISION DATE: May 2008

CITY OF HUNTINGTON BEACH

DEPARTMENT OF PUBLIC WORKS



GENERAL NOTES

STANDARD PLAN
100
4 of 4