



GENERAL NOTES:

1. ALL STEEL CASING PIPE FIELD JOINTS SHALL BE WELDED FULL CIRCUMFERENCE.
2. PERIPHERY OF CASING TO BE PRESSURE GROUTED.
3. CARRIER PIPE SHALL BE AIR TESTED PRIOR TO FILLING CASING WITH GROUT.
4. UPSTREAM AND DOWNSTREAM ELEVATIONS OF CARRIER PIPE TO BE VERIFIED PRIOR TO FILLING CASING.

APPROVED:

CITY ENGINEER

REVISION DATE:            MAY 2008.

CITY OF HUNTINGTON BEACH

DEPARTMENT OF PUBLIC WORKS



STEEL CASING PIPE

STANDARD PLAN

512

1 of 1